




RTX-63C-VET, RTX-64C-VET, RTX-65C-VET

Dakota Digital RTX Instrument Installation For 1963-1967 Chevy Corvette

Your new RTX-6XC-VET kit includes:


RTX Display





Installation


1. Remove the stock gauges from the dash. Remove the 10 screws holding the gauges to the bezel on the back of the system




2. Remove the stock gauges. To remove the lens separator plate, remove the nuts. The only item to be reused is the original front bezel; the other pieces can be set aside.




3. With the lenses and lens separator removed, place the included block off parts in the appropriate spaces. Use RTV silicone to secure the block off pieces in place. NOTE: Make sure the smooth side of the plastic with the part number is facing you when installing.



4. Using the 10 factory screws from Step One, secure the RTX gauge assembly to the bezel.



5. Connect the provided harness and the buzzer (optional for audio feedback) to the back of the RTX system.



6. Re-install the cluster into the car and refer to the main manual for wiring instructions to complete the RTX installation.



▲ WARNING: This product can expose you to chemicals including lead, which is known to the State of California to cause cancer and birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov



4510 W. 61st St. North Sioux Falls, SD 57107 www.dakotadigital.com dakotasupport@dakotadigital.com Phone (605) 332-6513 Fax (605) 339-4106

© Copyright 2020 - Dakota Digital